

Notes:

- 1. Supply and erect Advance Works notice board on 'A' frame, maintain and subsequently remove.
- The contractor is to insert the dates as appropriate and is responsible for updating any change of programme.
- 3. Location of signs to be agreed with the *Overseeing Organisation*.
- Signs to be erected 14 days in advance of the works, or as agreed by the Overseeing Organisation.

Scheme Ref.				
Sign Reference	SIGN 1	'x'-height	50.0	
Letter colour	BLACK	SIGN FA	SIGN FACE	
Background	YELLOW	Width	1155mm	
Border	BLACK	Height	1430mm	
Material	Class-1	Area	1.65sq.m	



COUNTY HALL Pegs Lane Hertford, Herts SG13 8DN

Phone: 01992 555555

Revisions

A -

В-

C-

Drawing Title

WORKS SIGNS STANDARD LAYOUT 1 Dwg No: HST/0100/005

Scale at A4: NTS

3000 0174 : N. 1.3.				
Drawn	Approved	Revised		
PAS	JE			
Checked	Date	Date		
STM	08/11			